



PLANNING &
DEVELOPMENT
2101 O'Neil Avenue
Cheyenne, WY 82001
(307) 637-6282
cheyennecity.org

MEMO

To: Honorable Mayor Patrick Collins and Members of the City Council
From: Connor White
Subject: PUDC-26-176 / Orchard Hills – Future Land Use Map Amendment
Date: September 14, 2026

Background:

The item for consideration is a Future Land Use Map Amendment (or Comprehensive Plan Amendment). This is approved by Resolution.

The proposed Governing Body review schedule is as follows:

- Introduction and Referral September 14, 2026
- Public Services Committee September 21, 2026
- Final Consideration October 12, 2026

Planning Commission Recommendation:

The Planning Commission heard this item at their September 8, 2026, meeting and unanimously voted against the amendment. Approval of this motion was essential for the associated zone change, and the Planning Commission used this to influence their recommendation on the associated zone change (see the zone change staff report for more information on that item). A Resolution overruling the Planning Commission's disapproval is required and is a separate item on the Council agenda.

At the Public Services Committee meeting on September 14, 2026, Staff will request that this item be postponed until the October 12, 2026 City Council meeting to line up with the annexation and zoning map amendment should Council wish to move these items forward. The reason for introducing this item early is so that all items related to the Orchard Hills development can be discussed at the same time.

The Planning Commission Staff report is attached and unchanged.

County Commissioner Comment:

The amendment procedures in PlanCheyenne require proposed amendments entirely within City limits (or going to be within City Limits upon final consideration) to go to the County Commissioners for comment only. The County Commissioners will hear this item at their meeting on September 15, 2026.

Public Comment

Between the publication of the Planning Commission Staff Report and the publication of this memo (September 9, 2026), Staff has received no new inquiries or comments from the public on this project. The project page on the website has received 191 views and no comments.

Attachments:

1. Resolution
2. Planning Commission Staff Report

RESOLUTION NO. _____

ENTITLED: "A RESOLUTION AMENDING THE FUTURE LAND USE MAP OF PLANCHEYENNE CHANGING THE LAND USE DESIGNATION FROM MIXED-USE RESIDENTIAL TO MIXED-USE EMPLOYMENT FOR PROPERTY GENERALLY LOCATED WEST OF SOUTH GREELEY HIGHWAY, SOUTH OF WEST COLLEGE DRIVE, AND SOUTHWEST OF AND ADJACENT TO THE INTERSECTION OF APPLE STREET AND YORK AVENUE."

WHEREAS, *PlanCheyenne*, as amended by *PlanCheyenne: Reflections and Progress* adopted by the Governing Body of the City of Cheyenne by Resolution No. 5573, is the Master Plan for the City of Cheyenne and the Comprehensive Plan for portions of Laramie County adopted by both the Governing Body of the City of Cheyenne and Laramie County Board of County Commissioners;

WHEREAS, the intent of the Future Land Use plan is not to predetermine specific land uses for individual parcels or specific locations for uses or facilities, but to provide a general framework for neighborhoods and activity centers organized around roadway networks and major parks and open space;

WHEREAS, Trey Rinne of AVI, PC, a resident within Cheyenne, has initiated an amendment to the Future Land Use map to amend the land use category from Mixed-use Residential to Mixed-use Employment for land described as:

A PARCEL OF LAND BEING THE SW1/4 OF SECTION 18, TOWNSHIP 13 NORTH RANGE 66 WEST OF THE 6TH PRINCIPAL MERIDIAN, LARAMIE COUNTY, WYOMING AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE WEST ONE-QUARTER CORNER OF SECTION 18; THENCE S89°53'10"E A DISTANCE OF 1377.66 FEET; THENCE S89°54'17"E A DISTANCE OF 1317.22 FEET; THENCE S00°14'44"W A DISTANCE OF 2626.16 FEET TO THE SOUTH ONE-QUARTER CORNER OF SAID SECTION 18; THENCE ALONG THE SOUTH LINE OF SAID SECTION 18 S89°59'18"W A DISTANCE OF 2687.83 FEET TO THE SOUTHWEST CORNER OF SAID SECTION 18; THENCE ALONG THE WEST LINE OF SAID SECTION 18 N00°05'31"E A DISTANCE OF 2631.62 FEET MORE OR LESS TO THE POINT OF BEGINNING;

WHEREAS, Plan Amendments are approved by the Governing Body pursuant to the criteria set forth on Page 18 of *PlanCheyenne*, as amended;

WHEREAS, the Laramie County Board of County Commissioners reviewed the proposed future land use map amendment and were given the opportunity to make comments;

WHEREAS, a public hearing to receive public input and comments on the proposed Future Land Use map amendment for the above-described property was held before the City of Cheyenne Planning Commission on September 8, 2026; and

WHEREAS, Plan Amendment processes and procedures required by *PlanCheyenne*, as amended, have been followed with regard to the request by Trey Rinne to amend the Future Land Use map category for the above-described property.

NOW, THEREFORE, BE IT RESOLVED BY THE GOVERNING BODY OF THE CITY OF CHEYENNE, WYOMING, that the City of Cheyenne Governing Body hereby amends the Land Use Plan for *PlanCheyenne* changing the land use category from Mixed-Use Residential to Mixed-use Employment, as shown in Exhibit A, in accordance with the procedures outlined in *PlanCheyenne* and Wyoming Statutes § 15-1-503 and § 15-1-505;

BE IT FURTHER RESOLVED, that staff is authorized to amend affected maps of *PlanCheyenne* to reflect the aforementioned changes; and

BE IT FURTHER RESOLVED, that this resolution shall become effective after its passage, approval, and signing by the Mayor.

PRESENTED, READ AND ADOPTED this _____ day of _____, 2026.

PATRICK COLLINS, MAYOR

(SEAL)

ATTEST:

KYLIE SODEN, CITY CLERK



FILE:	PUDC-26-176: Orchard Hills – Comprehensive Plan Amendment
REQUEST:	A request to amend the Future Land Use Map of the Comprehensive Plan from Mixed-use Residential to Mixed-Use Employment for approximately 162.42 acres; Also to amend the Major Street Plan.
LOCATION:	West of South Greeley Highway, south of West College Drive, and southwest of and adjacent to the intersection of Apple Street and York Avenue.
AGENT:	Trey Rinne, AVI, P.C.
OWNER:	Orchard Hills LLC
ZONING:	Current: County LU – Land Use Proposed: LI – Light Industrial
FUTURE LAND USE:	Proposed Mixed-use Employment (Current – Mixed-use Residential)
PURPOSE:	To support rezoning of land to LI – Light Industrial.
PREPARED BY:	Connor White, Planner II



RECOMMENDED MOTION:

Move to **deny** the Resolution amending the Future Land Use Plan and Master Transportation Plan for land located west of South Greeley Highway, south of West College Drive, and southwest of and adjacent to the intersection of Apple Street and York Avenue as shown in Exhibit A changing the Future Land Use Map from Mixed-use Residential to Mixed-Use Employment due the request not meeting the review criteria 1, 2, 7, and 8.

APPLICABLE CITY CODE SECTION(S) AND PLANS:

- PlanCheyenne

BACKGROUND:

The applicant is requesting amending the Future Land Use Map for roughly 162.42 acres of land from Mixed-use Residential to Mixed-Use Employment to accommodate a zone change to Light Industrial for future development. The applicant has not specified a proposed use for the property; however, they have indicated verbally in meetings that data center development is anticipated.

The property is shown as Mixed-use Residential in the Future Land Use Plan. The Mixed-Use Residential category promotes self-supporting neighborhoods that primarily contain housing. A range of residential housing types, such as single-family residences, duplexes, patio homes, townhomes, apartments, condominiums, and live-work units, should be built on a majority of any site within this category. The Mixed-use Residential designation considers the MUR Mixed-use Residential zone as the optimal zone district; however, various residential zones and lighter-intensity commercial zones may also be appropriate.

The property to the south was designated as Urban Residential and Mixed-use Residential until 2022 when it was changed to Mixed-use Employment. When that area was changed, it was to help spur development in the area and allow for the extension of both water and sewer to help remove the barrier of utility extensions for residential development.

A concurrent application for a zoning map amendment requesting LI – Light Industrial zoning has been submitted. The zoning map amendment will accompany the future land use amendment at City Council. If the application for the zoning map amendment is approved, the applicant will be required to submit a site plan application for the new development.

SURROUNDING LAND USE AND ZONING:

	Future Land Use Designation	Zoning District	Land Use
Subject Site	Mixed-use Residential	County LU – Land Use	Vacant
North	Urban Residential	County LU Land Use, County URLD – Urban Residential Low-density	Single-family Residential, Utility Substation
South	Mixed-use Employment	LI – Light Industrial	Data Center

East	Mixed-use Residential	County LU	Vacant
West	Mixed-use Residential	County LU	Vacant

ANALYSIS OF APPLICATION CONFORMANCE WITH REVIEW CRITERIA:

Should the Planning Commission wish to approve an amendment to the Future Land Use Map of the Comprehensive Plan, the Commission must make the following considerations outlined in the 2014 Community Plan (Build Chapter page 3-3). A detailed analysis is below:

1) BENEFICIAL OR ADDRESSES ISSUES - The proposed amendment is beneficial to the community or addresses issues not foreseen during the planning process.

This review criterion has two parts, each of which will be addressed individually.

Regarding if the proposed amendment is beneficial to the community:

The proposed amendment has been requested to allow LI Light Industrial zoning. The Land use category requested supports business-campus style development focused primarily on office and light industrial uses and is similar to the development patterns of North Range, Swan Ranch and High Plains Business Parks. Retail and service uses may be included as supportive secondary uses to support the campus style development and its employees. Higher-intensity employment uses are encouraged near major roadways and residential development is typically not supported in these districts. However, to take the portions of this property designated residential out of the residential designation would be to take away areas that would be suitable for residential development. The City of Cheyenne has a housing shortage and it may not be appropriate to remove areas designated for some sort of residential development that could become residential subdivisions or multifamily development.

Regarding if the proposed amendment addresses unforeseen issues:

The subject property and adjacent properties to the east and west are designated with Mixed-use Commercial, while to the north is Urban Residential. To the south is Mixed-use Employment. Over the recent years Cheyenne has seen an increase in industrial development which was not anticipated in 2014. Much of the industrial development has been large scale and on large acres of land. While some business parks have available land for development, much has been taken up already.

The proposed Future Land Use amendment may address unforeseen issues but is overall not a benefit to the community as it reduces an area planned for residential. The proposed amendment **does not comply** with review criterion 1.

2) COMPATIBLY - The proposed amendment is compatible with the surrounding area, and the goals and policies of the Plan.

The current situation surrounding this property includes light industrial zoning to the south, urban residential low-density to the north/northeast and LU Land Use to the west/northwest and east. The surrounding development patterns in the surrounding areas includes mainly single-family residential to the north/northeast, vacant land to the west and east and a data center to the south. There is also a power substation to the northwest.

The goals of the current future land use map in the surrounding area is to have mainly residential development with a slight mix of commercial development in the area. Residential has been developing to the north/northeast and further to the east. Nearby investment in the area includes a new 5-6 elementary school within a 1/2 mile of the area proposed for change. Industrial development has developed to the south on a single large lot.

The proposed Future Land Use amendment largely **does not comply** with review criterion 2.

3) IMPACT MITIGATION - The proposed amendment will address and mitigate impacts on transportation, services, and facilities.

Transportation:

There are no current proposed changes to the Master Transportation plan for the area. Parsley Blvd is being evaluated in an MPO Study that may lead to amendments to the Major Street Plan in the area.

Any development that occurs in this area will have to address transportation issues. Industrial-style development will have different transportation needs and different funding for infrastructure improvements than residential or commercial development.

Right-of-way dedication and improvements will be required in conjunction with future development actions such as platting.

Services:

The proposed change will not have any adverse effects on provision of services to the subject property. This area of the community has access to water and sewer services.

Facilities:

The proposed change will not have any adverse effects on facilities.

The proposed Future Land Use amendment **complies** with review criterion 3.

4) SERVICE PROVISION - The proposed amendment will have minimal effect on service provision, including adequacy or availability of urban facilities and services, and is compatible with existing and planned service provision

The proposed change will not have any adverse effects on provision of services to the subject property.

The proposed Future Land Use amendment **complies** with review criterion 4.

5) ANNEXATION - The proposed amendment does not jeopardize the City's ability to annex the property.

The subject property is currently proposed to be annexed into City limits.

The proposed Future Land Use amendment **complies** with review criterion 5.

6) URBAN SERVICES AREA - The proposed amendment is consistent with the logical expansion of the Urban Services Area.

This land is currently within the Urban Services Area.

The proposed Future Land Use amendment **complies** with review criterion 6.

7) STRICT ADHERENCE - Strict adherence to the Plan would result in a situation neither intended nor in keeping with other key elements and policies of the Plan.

Strict adherence to the Plan would result in a mix of residential and some commercial development in an area of the community with ready access to services and the transportation network. Development in this area would create areas that are walkable to the existing greenway system and two elementary schools (Afflerbach and Rossman), a 5-6 school (Mountain View) and a high school (Triumph) which are all between a half-mile to full-mile of the area proposed for change.

The proposed Future Land Use amendment largely **does not comply** with review criterion 7.

8) PUBLIC WELFARE AND CONSISTENCY – The proposed plan amendment will promote the public welfare and will be consistent with the goals and policies of PlanCheyenne and the elements thereof.

No specific use has been identified for this area. The evaluation of this land use plan amendment and the related zoning should be based on all possible alternatives in the desired zone districts supported by the Mixed-use Employment land use category. Once this property is changed to Mixed-use Employment, other large acres of land in the area might domino into industrial development and opportunities for future permanent housing in this area may be lost. Housing is a defined need of the community, and it would be detrimental to the public welfare to take land anticipated for urban residential development and change it to non-residential uses.

Policies in PlanCheyenne are mixed on this proposal, but, on the balance, probably would encourage maintaining the current land use designation.

Consideration of various policies of PlanCheyenne in regard to this proposal:

- **Policy 1.1.B. Flexibility to Market Demands:** This goal notes that the Future Land Use Plan does not predetermine all uses on individual parcels and is meant to provide flexibility. The future land use map amendment to Mixed-use Employment will allow for more commercial or industrial uses and may recognize a potential trend of this area becoming more industrial in nature.
- **Policy 2.5.A. Community Housing Met:** This goal notes that the availability and attainability of housing is a concern for the community. Changing the future land use map amendment to Mixed-use Employment will reduce the ability for Cheyenne to provide available permanent housing connected to existing residential neighborhoods.
- **Principle 3.5 Provide opportunities for a range of industrial employment uses:** This goal encourages Cheyenne to leverage rail and interstate access for a range of industrial uses. Large-scale data centers may be utilizing large swaths of existing industrial parks, creating the need for new industrial areas located near interstates or railroads. The future

land use map amendment to Mixed-use Employment at this location will allow for more industrial uses in close proximity to interstates.

The proposed Future Land Use amendment largely **does not comply** with review criterion 8.

CONFORMANCE WITH APPLICABLE PLANS:

No other plans are applicable for this area.

PUBLIC NOTICE AND PUBLIC COMMENTS RECEIVED:

Although projects have public notice and the opportunity for public comments, projects are required to be approved or denied based on the review criteria (listed above). Public comments relevant to the review criteria may assist the review and discussion on the application.

The public was given notice of the project in the following ways:

- **Legal Notice** in the Wyoming Tribune Eagle published on August 22, 2026.
- **Mailed Notice.** Evidence of mailed notice was provided showing that the letters were mailed on August 13, 2026.
- **Posted Notice.** Evidence of posted notice was provided on September 1, 2026.
- **Internet Posting** on connect.cheyennecity.org on July 13, 2026.

As of the publication of the Staff Report (September 1, 2026), Staff has received one inquiry from the public on this project and a letter supporting the proposed change (attached). The project page on the website has received 165 views and no comments.

STAFF REVIEW:

Through the review process, review comments were received expressing concerns about the appropriateness of the Mixed-use Employment designation at this location. Staff also noted that drainage and traffic will have to be reviewed in further detail and appropriately addressed with future development actions like platting and site plan.

CONCLUSION:

Despite the LI zoning and industrial development existing to the south of the property, much of the area is developed with residential and was anticipated to be residential. It was only recently that the area to the south was changed from Urban Residential and Mixed-use Residential to Mixed-use Employment and the impetus for allowing that change was to help open the door for residential or commercial development to the north as infrastructure was extended into this area.

ALTERNATIVES:

1. Approve the Resolution amending the Land Use Plan as submitted by the applicant (**Staff Recommendation**).
2. Approve the Resolution amending the Land Use Plan subject to modifications.

3. Deny the Resolution to not amend the Land Use Plan. The Planning Commission must conclude that the project does not meet all the review criteria. As part of the motion, findings for denial must be stated.
4. Postpone the Resolution until issues identified during the meeting can be resolved.

General Information Regarding Alternatives:



In the event that the Commission acts contrary to staff's recommendation, the Commission shall cite specific reasons (based on the review criteria) for approval or denial.

STAFF RECOMMENDATION:

Staff recommends denial of the Resolution amending the Future Land Use Map for land west of South Greeley Highway, south of West College Drive, and southwest of and adjacent to the intersection of Apple Street and York Avenue as shown in Exhibit A from Mixed-use Residential to Mixed-Use Employment and amending the major street plan.

ATTACHMENTS:

1. Zoning Map
2. Land Use Plan Map
3. Application
4. Exhibit A – Applicant-provided map of area to be amended.
5. Neighbor Comment Letter





Attachment 1: Zoning Map PUDC-26-176

This map/data is made possible through the Cheyenne and Laramie County Cooperative GIS (CLCCGIS) Program and is for display purposes only. The CLCCGIS invokes its sovereign and governmental immunity in allowing access to or use of this data, makes no warranties as to the validity, and assumes no liability associated with the use or misuse of this information.

Legend

- Nov19_CityLimits
- Interstate
- Principal Arterial
- Minor Arterial
- Major Collector
- Minor Collector
- Local
- Private
- Platted not built
- HR / High Density Residential
- MR / Medium Density Residential
- LR / Low Density Residential
- NR-2 / Neighborhood Residential - Med. Density
- NR-3 / Neighborhood Residential - High Density
- AR / Agricultural Residential
- A-1 / Agricultural and Rural Residential
- A-2 / Agricultural
- AG / City Agricultural
- MUR / Mixed Use Residential Emphasis
- CBD / Central Business District
- CB / Community Business
- NB / Neighborhood Business
- MU / Mixed Use - County
- MUB / Mixed Use Business Emphasis
- MUE / Mixed Use Employment Emphasis
- HI / Heavy Industrial
- LI / Light Industrial
- P / Public
- AD / Airport District
- PUD / Planned Unit Development
- X / Exempt



Attachment 2: Land Use Map PUDC-26-176

This map/data is made possible through the Cheyenne and Laramie County Cooperative GIS (CLCCGIS) Program and is for display purposes only. The CLCCGIS invokes its sovereign and governmental immunity in allowing access to or use of this data, makes no warranties as to the validity, and assumes no liability associated with the use or misuse of this information.

Legend

City Limits	Agricultural/Rural	Industrial
Interstate	Rural Residential	Central Business District
Principal Arterial	Urban Transition Residential	Community Business
Minor Arterial	Urban Residential	Public and Quasi-Public
Major Collector	Mixed-Use Residential	Military/Federal
Minor Collector	Mixed-Use Commercial	Open Space and Parks
Local	Mixed-Use Employment	
Platted not built		
Ownership		

Record No: PUDC-26-176

Comprehensive Plan Amendment

Status: Active

Submitted On: 7/8/2026

Primary Location

O DRAPER RD
Cheyenne, WY 82007

Owner

ORCHARD HILLS LLC
506 SHOSHONI ST CHEYENNE, WY 82009

Application

This application has a deadline. The deadline is the second Wednesday of the month.
Application Schedule.

Project Name* ?

Orchard Hills

Is this application proposing amending the Future
Land Use Map?*

Yes

Is this application proposing amending the text of
the Plan?*

No

Review Criteria

The following review criteria are found in PlanCheyenne regarding a Comprehensive Plan amendment. Please acknowledge the proposed amendment meets each review criterion by checking the box.

1. The proposed amendment is beneficial to the community or addresses issues not foreseen during the planning process.*



2. The proposed amendment is compatible with the surrounding area, and the goals and policies of the Plan.*



3. The proposed amendment will address and mitigate impacts on transportation, services, and facilities.*



4. The proposed amendment will have minimal effect on service provision, including adequacy or availability of urban facilities and services, and is compatible with existing and planned service provision.*



5. The proposed amendment does not jeopardize the City's ability to annex the property.*



6. The proposed amendment is consistent with the logical expansion of the Urban Services Area.*



7. Strict adherence to the Plan would result in a situation neither intended nor in keeping with other key elements and policies of the Plan.*



8. The proposed plan amendment will promote the public welfare and will be consistent with the goals and policies of PlanCheyenne and the elements thereof.*



Certification

A resident of Cheyenne or the plan area of Laramie is required to submit an application for a comprehensive plan amendment.*

I, the applicant, am a resident of Cheyenne (or the plan area of Laramie County).

I hereby certify that I am the owner, applicant, or agent named herein and that I have familiarized myself with the rules and regulations with respect to the filing of this application and that the foregoing statements and answers contained on this application and accompanying documents are true and accurate to the best of my knowledge.*

 **Trey Rinne**
Jul 8, 2026

Attachments

Proposed Comprehensive Plan Amendment Map


5081 FUTURE LAND USE AMENDMENT_9-1-26.pdf

Uploaded by Trey Rinne on Sep 1, 2026 at 3:54 PM

REQUIRED



 2 Versions



Letter of Authorization

Orchard Hills_Letter of Authorization.pdf

Uploaded by Trey Rinne on Jul 8, 2026 at 3:07 PM




Peition to change the Comprehensive Plan

REQUIRED

Orchard Hills_Future Land Use Amendment.pdf


Uploaded by Trey Rinne on Jul 8, 2026 at 3:39 PM



Orchard Hills TAZ Modeling

AVI Orchard Hills Model Results Memorandum_DRAFT_2026-06-05.pdf

Uploaded by Trey Rinne on Jul 8, 2026 at 3:41 PM



PUDC-26-176 Application Letter

PUDC-26-176 Application Letter.pdf

Uploaded by Connor White on Jul 21, 2026 at 8:33 AM

Charles Bloom
City of Cheyenne Planning and Development Director
2101 O'Neil Ave
Cheyenne, WY 82001

July 8, 2026

RE: FUTURE LAND USE AMENDMENT OF PROPERTY OWNED BY ORCHARD HILLS LLC

Dear Mr. Bloom

As a resident of Cheyenne please accept this request to amend the Future Land Use Plan for land described as SW1/4, Section 18, T13N, R66W.


The property is currently a vacant parcel and looking to be developed for a data center campus. It is requested to be changed from Mixed Use Residential to Mixed Use Employment. The area is going through the zoning process as well and is being requested to be zoned LI – Light Industrial.

The requested amendment is consistent with the broader vision of the City's Comprehensive Plan by encouraging orderly development and thoughtful land use planning as the UDC contemplates this area already with some mixed use employment. The parcel is neighbored to the north by an existing electrical substation and to the south by the Meta Data Center Campus making the proposed use appropriate.

If you have any questions or would like to discuss this project in greater detail, please contact me directly.

Respectfully Submitted
AVI PROFESSIONAL CORPORATION

Trey Rinne PE
1103 Old Town Lane | Cheyenne, Wyoming 82009 | 307.637.6017
2290 E Prospect Road Suite 5, Fort Collins, Colorado 80524 | 970.420.0086
avi@avipc.com | www.avipc.com





EXISTING PLAN CHEYENNE FUTURE LAND USE

- MIXED USE EMPLOYMENT
- MIXED USE RESIDENTIAL
- OPEN SPACE AND PARKS
- PUBLIC AND QUASI-PUBLIC
- URBAN RESIDENTIAL
- NATURAL/CULTURAL RESOURCE AREA
- FUTURE MAJOR COLLECTOR
- FUTURE MINOR ARTERIAL

PROPOSED AMENDMENT TO FUTURE LAND USE

- MIXED USE EMPLOYMENT
- MIXED USE RESIDENTIAL
- OPEN SPACE AND PARKS
- PUBLIC AND QUASI-PUBLIC
- URBAN RESIDENTIAL
- NATURAL/CULTURAL RESOURCE AREA
- FUTURE MAJOR COLLECTOR
- FUTURE MINOR ARTERIAL



AMENDMENT TO PLAN CHEYENNE
FUTURE LAND USE MAP
FOR
HIGH PLAINS BUSINESS PARK
2ND FILING

BEING SITUATED IN A PORTION OF THE SW $\frac{1}{4}$ OF SECTION 18,
TOWNSHIP 13 NORTH, RANGE 66 WEST, OF THE 6TH P.M.,
LARAMIE COUNTY, WYOMING
PREPARED SEPTEMBER 2026

NO.	REVISION	DATE

PREPARED FOR:
**TRAMMELL CROW COMPANY
ORCHARD HILLS LLC**

PROJECT:
**HIGH PLAINS BUSINESS PARK
2ND FILING**

DRAWING TITLE:
**AMENDMENT TO PLAN CHEYENNE
FUTURE LAND USE MAP**



ENGINEERING
PLANNING
SURVEYING
PC

307.637.6017
1103 OLD TOWN LANE, SUITE 101
CHEYENNE, WY 82009
AVI@AVIPC.COM

DATE:	Sep 01, 2026
DRAWN BY:	
DESIGNED BY:	
CHECKED BY:	
JOB NO.:	5081
DRAWING NO.	1 OF 1

Re: Letter of Support for the Orchard Hills Project and "LI" zoning.

To Whom It May Concern:

I, Joseph D. SARA, own the property 2275 West College Dr.

My property is directly adjacent to the Orchard Hills Property. I hereby support the Orchard Hills annexation and zoning for Light Industrial ("LI") use. I hereby oppose that the Orchard Hills property be zoned residential.

Being a direct adjacent landowner, the development of Orchard Hills property affects me and the future of my property more than anyone else.

As such, I support the annexation and LI zoning for the following reasons:

- I support a single "light industrial" use of the adjacent property over dense housing and support this area trending towards light industrial development.
- I support the light industrial use be on City of Cheyenne water and sewer utilities rather than on well and septic systems.
- I recognize that there are direct benefits that my property will receive as a result of the Orchard Hills property being annexed and developed with a light industrial use that would not be possible if the Orchard Hills property be zoned residential.

For the foregoing reasons, I support the annexation of the Orchard Hills property and that it be zoned LI ("light industrial").

LANDOWNER

Signed: 

Name: Joseph D. SARA