



**PLANNING &
DEVELOPMENT**

2101 O'Neil Avenue
Cheyenne, WY 82001
(307) 637-6282
cheyennecity.org

MEMO

To: Honorable Mayor Patrick Collins and Members of the City Council
From: Morgan Dennis
Subject: PUDC-26-207 Hitching Post District – Zoning Map Amendment
Date: September 9, 2026

Background:

The item for consideration is a Zoning Map Amendment (zone change). This is approved by Ordinance.

The proposed Governing Body review schedule is as follows:

- Introduction and Referral 9/14/2026
- Public Services Committee 9/21/2026
- Second reading 9/28/2026
- Public Services Committee 10/5/2026
- Third and final reading 10/12/2026

Planning Commission Recommendation:

The Planning Commission heard this item at their September 8, 2026.

The Planning Commission Staff report is attached and has not been changed.

Public Comment

As of the creation of this memo (September 9, 2026), Staff has received no inquiries or comments from the public on this project. The project page on the website has received 89 views and no comments from the public.

Attachments:

1. Ordinance
2. Planning Commission Staff Report

ORDINANCE NO. _____

ENTITLED: "AN ORDINANCE AMENDING THE OFFICIAL ZONING MAP OF THE CITY OF CHEYENNE, CHANGING THE ZONING CLASSIFICATION FOR LAND LOCATED SOUTH OF INTERSTATE 80, SOUTHEAST OF OTTO ROAD, AND WEST OF INTERSTATE 25 FROM AG AGRICULTURAL AND LI LIGHT INDUSTRIAL TO BP BUSINESS PARK."

BE IT ORDAINED BY THE GOVERNING BODY OF THE CITY OF CHEYENNE, WYOMING:

Section 1. That the owner of real property located south of Interstate 80, southeast of Otto Road, and west of Interstate 25 has applied for a zoning map amendment for said property in accordance with Section 2.2.1, Zoning Map Amendment, of the Cheyenne Unified Development Code ("UDC").

Section 2. That on September 8, 2026, the City of Cheyenne Planning Commission conducted a public hearing, reviewed the proposed zoning map amendment that is the subject of this ordinance, and recommended approval of said zoning map amendment.

Section 3. That the Governing Body of the City of Cheyenne finds that the zoning map amendment that is the subject of this ordinance meets the criteria specified in Section 2.2.1.d of the UDC.

Section 4. That, in accordance with Section 2.2.1, Zoning Map Amendment, Section 5.1.2, Zoning Districts Established, and Section 5.1.3, Official Zoning Map, of the UDC, the aforementioned zoning map amendment application is hereby approved, and the zoning classification of the real property described below is hereby changed to BP Business Park:

PARCEL 1:

A portion of Sections 10, 11 and 15 Township 13 North, Range 67 West of the Sixth Principal Meridian, being more particularly described as follows:

Beginning at the northwest corner of Lot 1, Block 1, Clear Creek Subdivision, 1st Filing and a point on the westerly right of way of Interstate 80 being monumented by a found aluminum cap; thence along said westerly right of way the following courses and distances: S75°26'12"E a distance of 176.02 feet to a found right of way marker; thence S49°36'27"E a distance of 103.26 feet to a found aluminum cap on the westerly boundary of a parcel shown on the annexation map for City Ordinance #3840 recorded at book 2091 page 974 of the Laramie County records; thence along said westerly boundary N01°31'59"W a distance of 1260.99 feet to a found aluminum cap on the westerly boundary of a parcel shown on the annexation map for City Ordinance #3955 recorded at book 2289 page 1496 of the Laramie County records; thence along said westerly boundary N01°31'59"W a distance of 298.43

feet to a set aluminum cap; thence N58°25'18"E a distance of 480.15 feet to a found iron pipe on the north line of said Section 11; thence along said north line N89°41'04"W a distance of 638.35 feet to a set aluminum cap and point of intersection with the southerly right of way of Otto Road; thence along said southerly right of way S63°16'55"W a distance of 836.23 feet to a set aluminum cap; thence N26°43'05"W a distance of 250.00 feet to a found right of way marker and a point on the north right of way of Otto Road; thence along said north right of way the following courses and distances: S63°16'55"W a distance of 6246.80 feet to a found right of way marker; thence S63°28'05"W a distance of 2918.72 feet to a found aluminum cap; thence S07°05'46"E a distance of 1253.29 feet to a found aluminum cap on the west line of said Section 15; thence along said west line S00°34'22"W a distance of 61.57 feet to a point on the northerly boundary of said Lot 1, Block 1 of Clear Creek Subdivision; thence along said northerly boundary the following courses and distances: N74°21'24"E a distance of 1091.72 feet to a found aluminum cap; thence N74°56'39"E a distance of 800.73 feet to a found aluminum cap; thence N84°53'46"E a distance of 445.57 feet to a found aluminum cap; thence N84°52'55"E a distance of 799.46 feet to a found aluminum cap; thence S86°45'41"E a distance of 1942.86 feet to a found aluminum cap; thence N88°04'10"E a distance of 302.17 feet to a found aluminum cap; thence N87°37'51"E a distance of 1285.00 feet to a found aluminum cap; thence N87°38'02"E a distance of 1124.45 feet to a found aluminum cap; thence N37°33'37"E a distance of 1369.83 feet to a found aluminum cap; thence N36°20'59"E a distance of 623.31 feet to a found aluminum cap; thence N00°00'09"E a distance of 1666.42 feet to the point of beginning.

AND

PARCEL 2:

A portion of Sections 11 and 14 Township 13 North, Range 67 west of the Sixth Principal Meridian, being more particularly described as follows:

Commencing at the northeast corner of said Section 14; thence N89°00'04"W a distance of 1804.32 feet to a found aluminum cap on the easterly boundary of Lot 1, Block 1 of Clear Creek Subdivision, 1st Filing and the point of beginning; thence S53°29'59"E a distance of 726.77 feet to a found aluminum cap; thence S14°08'25"W a distance of 341.22 feet to a found iron rod on the northerly boundary of Lot 1, Block 4 of Overland Trails Business Park Fourth Filing; thence along said northerly boundary N84°54'05"W a distance of 690.60 feet to a found aluminum cap on the westerly boundary of said Lot 1; thence along said westerly boundary S05°03'51"W a distance of 315.87 feet to a found iron rod; thence continuing along said westerly boundary S40°51'12"E a distance of 180.55 feet to a found aluminum cap on the westerly right of way of Clear Creek Parkway right of way and the beginning of a non-tangent curve to the left; said curve having a radius of 550.00 feet, a chord bearing of S30°17'31"W, a chord distance of 288.83 feet and a central angle of 30°26'44", thence along said westerly right of way and

the arc of said curve a distance of 292.26 feet to a found aluminum cap; thence continuing along said westerly right of way the following courses and distances: S15°03'05"W a distance of 520.32 feet to a found aluminum cap and the beginning of a curve to the left; said curve having a radius of 1492.82 feet, a chord bearing of S05°04'31"W, a chord distance of 518.45 feet and a central angle of 20°00'00", thence along the arc of said curve a distance of 521.09 feet to a found aluminum cap; thence S02°19'01"E a distance of 21.74 feet to a found aluminum cap and a point on the northerly boundary of Lot 1, Block 1 of Swan Ranch Rail Park 20th Filing; thence along said north boundary S73°17'44"W a distance of 432.70 feet to a set aluminum cap on the north-south quarter line of said Section 14; thence along said north-south quarter line N00°15'18"E a distance of 1333.44 feet to a set aluminum cap on the southerly boundary of said Lot 1, Block 1 of Clear Creek Subdivision; thence along said southerly boundary S88°00'30"E a distance of 76.82 feet to a found aluminum cap on said easterly boundary of Clear Creek Subdivision 1st Filing; thence along said easterly boundary N31°22'56"E a distance of 1448.54 feet to the point of beginning.

Section 5. That the City Engineer is hereby authorized and directed to alter and amend the Official Zoning Map as described in Section 5.1.3 of the UDC to comply with the zoning map amendment as described in Section 4 above when this ordinance takes effect in accordance with Section 7 below.

Section 6. Sections, paragraphs, sentences, clauses and phrases of this ordinance are severable. If any section, paragraph, sentence, clause, or phrase of this ordinance is declared unconstitutional, such unconstitutionality shall not affect any of the remaining sections, paragraphs, sentences, clauses, and phrases.

Section 7. That this ordinance shall be in full force and effect upon its approval and publication.

FIRST READING:

SECOND READING:

THIRD AND FINAL READING: _____

PATRICK COLLINS, MAYOR

(SEAL)

ATTEST:

KYLIE SODEN, CITY CLERK

Published: _____
Wyoming Tribune-Eagle

CITY OF
CHEYENNE
— PLANNING & —
DEVELOPMENT

CITY OF CHEYENNE PLANNING COMMISSION

September 8, 2026

STAFF REPORT

FILE: PUDC-26-207: Hitching Post District - Zoning Map Amendment (zone change)

REQUEST: A request to rezone approximately 652.67 acres of land from AG Agricultural and LI Light Industrial to BP – Business Park

LOCATION: South of Interstate 80, southeast of Otto Road, and west of Interstate 25

APPLICANT: Doug Samuelson, Swan Ranch LLC & Clear Creek Land Co LLC

AGENT: AVI P.C.


OWNER: Doug Samuelson, Swan Ranch LLC & Clear Creek Land Co LLC

ZONING: AG Agricultural and LI Light Industrial

FUTURE LAND USE: Agricultural/Rural

PURPOSE: Change the zone of this parcel from AG Agricultural and LI Light Industrial to BP Business Park.

PREPARED BY: Morgan Dennis, Planner I



RECOMMENDED MOTION:

Move to **approve** the rezoning of the Hitching Post District to BP Business Park as shown in the attached zone change map, noting that the project meets the review criteria for approval.

APPLICABLE CITY CODE SECTION(S) AND PLANS:

- UDC 2.2.1 Zoning Map Amendment
- UDC Article 5
- PlanCheyenne

BACKGROUND:

This zone change application proposes changing the zoning from Agricultural and Light Industrial to Business Park for roughly 652.67 acres of land. The land is currently vacant with sewer and water extension in the area. The proposal is to allow a large-scale destination facility which may include offices, a museum, or other accessory uses. Although the facility itself will likely only occupy small portion of the region, uses which may want to locate near this use may follow and utilize other land in the area proposed to be rezoned.

SURROUNDING LAND USE AND ZONING:

	Future Land Use Designation	Zoning District	Land Use
Subject Site	Agricultural/Rural, Mixed-Used Employment, Open Space and Parks	Overland PUD, County LI Light Industry (AG Agriculture and LI Light Industrial as assigned zones)	Vacant
North	Industrial/Community Business/Mixed-Use Employment	CB Community Business, County CB Community Business, County LU Land Use	Vacant, Lodging, Hotel/Motel
South	Agriculture/Rural, Industrial, Mixed-Used Employment, Open Space and Parks	AG Agricultural, Overland PUD, County LI Light Industrial, BP Business Park	Vacant, Service Business, Outdoor Sales, Automobile Service Station, Food Service
East	Agriculture/Rural, Community Business, Mixed-Used Employment, Mixed-Use Residential, Urban Residential, Open Space and Parks	Overland PUD, County CB Community Business, CB Community Business, County LU Land Use, AR Agricultural Residential, LI Light Industrial, Mixed-Used Business	Vacant, Single-family residential, Outdoor Storage, Recreational Vehicle Park, Service Business, General Industrial
West	Industrial, Rural Residential, Agriculture/Rural, Open Space and Parks	County LU Land Use, LI Light Industrial, Overland PUD	Vacant

ANALYSIS OF APPLICATION CONFORMANCE WITH REVIEW CRITERIA:

Should the Planning Commission wish to recommend approval of the Zoning Map Amendment, the Commission must make the following findings required in UDC 2.2.1.d. A detailed analysis is below:

1) The application is in accordance with the development policies and physical patterns identified in the Comprehensive Plan. (UDC 2.2.1.d.1)

These parcels are currently undergoing a Future Land Use Map Amendment to change designation from Agriculture/Rural and Rural Residential to Community Business to be in accordance with development and physical patterns. The Community Business designation supports a range of commercial activities, regional malls, and allows for offices, hotels, and service businesses. Intensive industrial activities are not appropriate. Secondary uses can open space and recreation, and other public or civic uses are appropriate. Multi-family housing may be appropriate if designed as part of an integrated mixed-use concept plan. Ideal locations for this designation are at interstate interchange or at the intersection of arterial or state highway. This designation aligns with the potential development Commercial/Regional Activity Centers.

Foundation 1 of PlanCheyenne does allow for flexibility in the future land use map based on market. This same Foundation promotes working with local and regional economic development partners to position Cheyenne as a place to live and do business in the Northern Front Range region.

Foundation 3 of PlanCheyenne focuses on Cheyenne becoming a favorable business environment through the development of regional activity centers. These commercial activity centers should be pedestrian-based and well designed.

Based on the policies and future land use map, BP Business Park would be appropriate in this area.

The proposed zone change **complies** with review criterion 1.

2) The application is compatible with nearby property, specifically considering existing zoning, the Comprehensive Plan, and any other official plans and policies created under the guidance of that plan for these areas; (UDC 2.2.1.d.2)

The proposed BP zone district would extend existing BP zoning from the south. The southern property is adjacent to BP zoning, and the BP zone specifically anticipates intervening interstates or natural areas (like floodplains) – the AG zoned parcel between these two parcels area is located along a waterway with floodplain. The northern properties are zoned County LU Land Use and City CB Community Business; the County LU Land Use parcels are vacant, and the CB Community Business parcels have the use of Lodging, Hotel/Motel. The remaining parcel around the largest parcel is zoned AG Agricultural and is vacant. The eastern parcels surrounding the smaller parcel are zoned P Public and Overland PUD and have developed commercial uses on them.

The existing zones are AG Agricultural and LI Light Industrial. AG Agricultural zoning allows for a limited amount of development options. LI Light Industrial allows for select commercial development and industrial development. Neither of the current zones would appropriately support the proposed end use(s) for this parcel.

The proposed zone change for the subject property **complies** with review criterion 2.

3) The suitability of the subject property for development according to the standards and uses of the existing zoning district, compared to the suitability of the subject property for development according to the standards and uses of the proposed zoning district (UDC 2.2.1.d.3)

The BP zone district allows for select service uses, a variety of commercial uses, and select industrial uses. The current use of the subject property is for vacant or agriculture proposed. In the County, the parcels were zoned within the Overland PUD. The Overland PUD created areas based on land use type. Within the annexed area, the land use types are Industrial, Business, and Open Space.

When annexed into the City, the land will be assigned the City zones of AG Agricultural and LI Light Industrial based on the current use of the property and previous County zoning. Based on the proposed development for this parcel, would need to fall under the UDC 6.9 General Commercial Design Standards. There is reduced landscaping requirements that may be inappropriate for the proposed development along with potential future development. Landscaping is vital in creating aesthetic pleasing character of new development and reduce visual harshness and summer heat. With the BP zone, majority of the landscaping will be focused on the parking lot and street frontage.

Running two weeks behind this zone change are various Ordinances that proposes changing parts of the Unified Development Code. The changes proposed in these ordinances would allow the BP Business Park zone district to include equestrian activities. The proposed end use for one of the platted parcel will involved equestrian activities.

The proposed zone change largely **complies** with review criterion 3.

4) The ability of the subject property and surrounding vicinity to be developed according to the Subdivision Standards in Article 4 considering the proposed zoning (UDC 2.2.1.d.4)

There are changes to the transportation network that will need to developed in accordance to Subdivision Standards in Article 4 and in coordination with Wyoming Department of Transportation future development plans.

The proposed zone change for the subject property **complies** with review criterion 4.

5) The ability of the application to support the Intent and Applicability statements of the proposed zoning district and achieve the Design Objectives of any specific standards. (UDC 2.2.1.d.5)

The BP district is intended to support small and large-scale industrial development while providing essential commercial services along regional transportation routes in an industrial park setting. The district integrates manufacturing, processing, research and development, and shipping activities in addition to retail, dining, and convenience stores to enhance functionality and appeal for businesses and employees.

These Business Park districts should be in area on the edge of the community that are intended to support large-scale industrial, manufacturing, shipping, research and development, and data center uses. These districts are typically found close to major transportation routes. The district has to be a minimum of 320 acres of land that can be interrupted by transportation routes and natural features. Large-scale areas within the future land use designations in the comprehensive plan of Community Business, Mixed-Use Employment, and Industrial – including Community/Regional Activity Centers are appropriate for BP zoning. The UDC also states that areas currently designated Agricultural/Rural may also be appropriate for this zone district if near to regional transportation routes and if development of the area extends appropriate infrastructure.

With the change in agricultural uses, equestrian uses will be allowed in the Business Park zone district. This was an important addition to the Business Park as part of the proposed development is facilities that would be used for equine events. With this change to the BP zone, it would make BP a more appropriate zone district for this use.

The future use of the area meets the intent and applicability of the BP zone district due to the location of the interstate interchange and the potential for a campus like development. The BP zone is meant for area of large area development, connective transportation routes, and the development of supportive uses.

The proposed zone change for the subject property **complies** with review criterion 5.

6) The ability of all potential future development to meet all applicable standards for development in the proposed zoning district, including other development options if any specific development proposed in association with the application is not executed after approval. (UDC 2.2.1.d.6)

The BP zone does allow for a variety of uses with a concentration on non-residential development. This is increase in amount of uses from the previous zone district of Agricultural and Light Industrial, which allowed for very few uses. All these uses will be needed to meet the applicable standards within the UDC.

The proposed use for this area are offices, a museum, and equine sport facilities. If for some reason this proposed use was unable to develop, it would still be able to develop into a commercial, service, or industrial use still. Due to access to the interstate, uses that could go into this area are restaurants, fast food or otherwise, hotels, and warehouse developments.

The proposed zone change **complies** with review criterion 6.

7) The review and recommendations of other reviewing bodies. (UDC 2.2.1.d.7)

No major comments received in regard to the proposed zone.

The proposed zone change for the subject property **complies** with review criterion 7.

**8) Whether the application will harm the public health, safety, or general welfare.
(UDC 2.2.1.d.8)**

City staff is satisfied that this proposed zone change would not adversely affect the public health, safety, or general welfare.

The proposed zone change for the subject property **complies** with review criterion 8.

CONFORMANCE WITH APPLICABLE PLANS:

The project is located in an area covered by the following plans:

- PlanCheyenne

Conformance with PlanCheyenne is covered by review criterion 1.

STAFF REVIEW:

Through the review process, review comments were received expressing the appropriateness of the BP zone at this location.

CONCLUSION:

Staff is satisfied that the application meets the review criteria set forth in UDC 2.2.1.(d). The BP zone is an appropriate zone based on the future land use map, surrounding zoning, surrounding development patterns, and proposed development.

ALTERNATIVES:

1. Recommend approval of the zoning amendment as submitted by the applicant (**Staff Recommendation**).
2. Recommend approval of the zoning amendment subject to conditions or modifications.
3. Recommend denial of the zoning amendment based on findings of denial. The Planning Commission must conclude that the project does not meet all the review criteria. As part of the motion, findings for denial must be stated.
4. Postpone the zoning amendment until issues identified during the meeting can be resolved.

General Information Regarding Alternatives:


If the Commission acts contrary to staff's recommendation or modifies conditions of approval, the Commission shall cite specific reasons (based on the review criteria) for approval or denial.


STAFF RECOMMENDATION:

Staff recommends approval of the rezoning of the property from AG and LI to BP.

ATTACHMENTS:

1. Current Zoning Map
2. Future Land Use Map
3. Master Application
4. Applicant Provided Zone Change Map





C* Cheyenne, WY

September 1, 2026

Record No: PUDC-26-207

Zoning Map Amendment

Status: Active

Submitted On: 8/12/2026

Primary LocationO OTTO RD
Cheyenne, WY 82007**Owner**SWAN RANCH LLC
1961 US HWY 85 CHEYENNE, WY 82009

Staff useStaff Report ready for publication ☐Final Decision ready for publication ☐City Initiated ☐

Application

This application has a deadline. The deadline is the second Wednesday of the month.
Application Schedule.

Project Name* 

Hitching Post District

Proposed Zoning* 

BP Business Park

Project Description or notes 

zone change from County PUD and LI to City BP

Review Criteria

The following review criteria are found in the UDC regarding a zoning map amendment. Please acknowledge the proposed zoning map amendment meets each review criterion by checking the box.

The application is in accordance with the development policies and physical patterns identified in the Comprehensive Plan (2.2.1.d.1).*



The application is compatible with nearby property, specifically considering existing zoning, the Comprehensive Plan, and any other official plans and policies created under the guidance of that plan for these areas (2.2.1.d.2).*



The suitability of the subject property for development according to the standards and uses of the existing zoning district, compared to the suitability of the subject property for development according to the standards and uses of the proposed zoning district (2.2.1.d.3).*



The ability of the subject property and surrounding vicinity to be developed according to the Subdivision Standards in Article 4 considering the proposed zoning (2.2.1.d.4).*



The ability of the application to support the Intent and Applicability statements of the proposed zoning district, and achieve the Design Objectives of any specific standards (2.2.1.d.5).*



The ability of all potential future development to meet all applicable standards for development in the proposed zoning district, including other development options in the event that any specific development proposed in association with the application is not executed after approval (2.2.1.d.6).*



The review and recommendations of other reviewing bodies (2.2.1.d.7). (Not applicable at time of application)

Whether the application will harm the public health, safety, or general welfare (2.2.1.d.8).*



Certification

I hereby certify that I am the owner, applicant, or agent named herein and that I have familiarized myself with the rules and regulations with respect to the filing of this application and that the foregoing statements and answers contained on this application and accompanying documents are true and accurate to the best of my knowledge.*

✔ Christine Johnson
Aug 12, 2026

Attachments

	Proposed Zoning Map 5110 ZONE CHANGe.pdf Uploaded by AVI P.C. on Aug 11, 2026 at 9:54 AM	REQUIRED
	Letter of Authorization swan loa_001.pdf Uploaded by AVI P.C. on Aug 10, 2026 at 4:55 PM	REQUIRED
	Draft Neighbor Notification Letter Zone Change Hitching Post.pdf Uploaded by AVI P.C. on Aug 11, 2026 at 9:25 AM	REQUIRED
	Neighbor Notification List Hitching Post Mailing List.xlsx Uploaded by AVI P.C. on Aug 11, 2026 at 9:27 AM	REQUIRED
	Photos of Posted Notice hitching post photo.jpeg Uploaded by AVI P.C. on Aug 26, 2026 at 7:22 AM	



Mailed Notice

img20260825_08094951.pdf

Uploaded by Morgan Dennis on Aug 25, 2026 at 10:23 AM



PUDC 26-207 Schedule Letter

PUDC 26-207 Application Letter.pdf



Uploaded by Morgan Dennis on Aug 13, 2026 at 1:27 PM



hitching post photo 2.jpeg

hitching post photo 2.jpeg

Uploaded by AVI P.C. on Aug 26, 2026 at 7:22 AM



A PARCEL OF LAND SITUATED IN PORTIONS OF SECTIONS 10, 15, AND 16, TOWNSHIP 13 NORTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, CITY OF CHEYENNE, LARAMIE COUNTY, WYOMING, CONSISTING OF ALL LANDS LYING WITHIN THE AREA BOUNDED BY LOT 1, BLOCK 1, CLEAR CREEK SUBDIVISION ON THE SOUTH AND EAST, AND THE INTERSTATE 25 / INTERSTATE 80 INTERCHANGE AND THE UPRR RAILROAD RIGHT-OF-WAY ON THE NORTH.

- EXISTING ZONING: COUNTY LI AND PUD
- PROPOSED ZONING: CITY BP
- PROPOSED USE: TO BE DETERMINED
- NUMBER OF TRIPS PER DAY: TO BE DETERMINED
- NEAREST FIRE HYDRANT: AS SHOWN

FOUND IRON ROD
FOUND WYDOT RIGHT OF WAY MARKER
FOUND STONE
SET ALUMINUM CAP
PROPOSED ZONING - CITY BP
EXISTING HYDRANT LOCATIONS
SECTION LINE

ZONE CHANGE MAP FOR HITCHING POST DISTRICT

A PARCEL OF LAND LOCATED IN A PORTION OF
SECTIONS 10, 11, 14, AND 15, TOWNSHIP 13 NORTH,
RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN,
LARAMIE COUNTY, STATE OF WYOMING
PREPARED JULY 2026

[illegible]

PREPARED FOR:

CHEYENNE LEADS

HITCHING POST DISTRICT

ZONE CHANGE



307.637.6017
1103 OLD TOWN LANE, SUITE 101
CHEYENNE, WY 82009
AVI@AVIPC.COM

DATE: Aug 11, 2026

DRAWN BY:	NG
DESIGNED BY:	

CHECKED BY: _____ AED

JOB NO.: 5110

DRAWING NO. 1 OF 1