

CITY OF CHEYENNE
CONTRACT MODIFICATION

APPROVED as to form only:
By John Brodie at 2:30 pm, May 21, 2025

Contract Modification: #1
Project: 2024 Dell Range Concrete Repair for Overlay
Project Number: Contract # 7991
Contractor: S&S Builders, LLC
Date Prepared: May 14, 2025

The above referenced contract is amended or modified as set forth in the following and these amendments and modifications of the plans and specifications are agreed to by the parties. All other aspects of the original agreement remain unchanged and in full force and effect.

I. Description of Changes

- a. Additional Pedestrian Pathway/Greenway upgrades abutting city-owned property along Windmill Road and connecting to Dell Range Boulevard. These upgrades will convert the existing pathway from deteriorating asphalt to concrete, improve drainage, and provide for safer pedestrian travel. (\$236,622.00). See Exhibit A, attached hereto and incorporated herein by reference.
- b. Additional concrete repairs throughout the Dell Range corridor due to unforeseen subgrade conditions, which have created a shortage of funds in the contract amount to complete all the scheduled work. (\$60,000.00).

II. New Contract Items

- a. The first new contract item regarding the additional \$236,622.00 contract amount is detailed as provided by Exhibit A, attached hereto and incorporated herein by reference.
- b. The second new contract item authorizes an increase in the contract value by \$60,000.00 to restore funds previously reallocated to address unanticipated conditions, including deteriorated concrete in deceleration lanes on Dell Range Boulevard and removal of buried concrete on Ridge Road. These additional costs impacted funding for remaining items such as thermoplastic crosswalks, curb and gutter, and asphalt patching. The added amount includes a contingency to cover any further miscellaneous needs as the project concludes.

III. Schedule

Due to the additional work included under this contract modification, the contract completion date is extended from May 31, 2025, to August 15, 2025.

IV. Summary

Original Contract Amount	\$3,157,624.01
Previous Modifications	\$0.00
Contract Amount Prior to this Modification	\$3,157,624.01
This Modification	\$296,622.00
New Contract Amount	\$3,454,246.01

V. GL Account Information

If requesting a modification to the contract price, please list GL account # to cover the balance of this modification (if using more than (1) GL account, list the dollar amount for each respective account):

GL# 032-17-1754-45-43416 Amount: \$236,622.00

GL# 021-26-2616-42-43493 Amount: \$60,000.00

VI. Approvals

City Project Manager: _____ Date: _____

Consultant/Contractor: _____ Date: _____

City of Cheyenne DATE: _____

_____/_____
Mayor Patrick Collins /ATTEST: City Clerk Kylie Soden

Exhibit A

PROJECT: 2025 Windmill Greenway replacement

BID TAB

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
	ADDENDUM #1 3/21/2025				
01000.01	PERFORMANCE BOND	BOND	1.00	1,250.00	\$1,250.00
01000.02	MOBILIZATION	LS	1.00	10,071.25	\$10,071.25
01000.03	FORCE ACCOUNT	FA	1.00	\$ 10,000.00	\$ 10,000.00
01050.01	TRAFFIC CONTROL, INCLUDES TWO MESSAGE BOARDS TO BE USED AT THE CITY'S DISCRETION.	LS	1.00	3,225.00	\$3,225.00
01563.00	SEDIMENT EROSION CONTROL AND STORM WATER MANAGEMENT	LS	1.00	2,500.00	\$2,500.00
02076.00	COLD ASPHALT MILLING AT 2.5-3 INCHES. MILL IN PLACE, COMPACT AND BASE OVER	SQYD	2,010.00	5.60	\$11,256.00
02210.01	UNCLASSIFIED EXCAVATION, (FOR ANY UNFORSEEN REMOVALS	CUYD	20.00	83.75	\$1,675.00
02210.02	IMPORT GRADING W, L, OR RECYCLED CONCRETE BASE. 4" AT STANDARD GREENWAY AND 6" AT APPROACHES (INCLUDES ADDITIONAL MATERIAL TO ADDRESS ANY LOW SPOTS)	TON	400.00	49.00	\$19,600.00
02515.01	BITUMINOUS PATCH, 6" ASPHALT AT APPROACH AREAS	SQYD	16.00	218.50	\$3,496.00
02900.03	TOPSOIL, 4" DEEP	SQYD	927.00	4.50	\$4,171.50
02900.04	DRYLAND GRASS SEED	SQYD	927.00	2.75	\$2,549.25
03340.01	REMOVE ASPHALT AND REPLACE WITH 8" CONCRETE SIDEWALK GREENWAY AT APPROACH CROSSINGS	SQFT	645.00	20.00	\$12,900.00

PROJECT: 2025 Windmill Greenway replacement

BID NO. S-17-25

BID TAB

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
03340.02	NEW SIDEWALK GREENWAY 4"	SQFT	18,086.00	8.00	\$144,688.00
03340.03	NEW CONCRETE DRAIN PAN 6" (BETWEEN GREENWAY AND ROADWAY DRAIN PIPES.	SQFT	120.00	22.00	\$2,640.00
0	18" DUAL WALL HDPE PIPE WITH GALVANIZED FLARED END SECTIONS, COMPLETE IN PLCE INCLUDING REMOVAL OF EXISTING PIPE	LNFT	20.00	330.00	\$6,600.00
TOTAL					\$236,622.00

COMPANY NAME: S & S Builders, LLC

ADDRESS: PO Box 20033 / 716 CR 128A

CITY, STATE, ZIP: Cheyenne, WY 82003

BIDDER'S SIGNATURE:

