



A COMMUNITY OF CHOICE

CITY ENGINEER'S OFFICE
2101 O'Neil Avenue
Cheyenne, Wyoming 82001

MEMO

TO: Honorable Mayor Patrick J. Collins, City of Cheyenne
Members of the City Council, City of Cheyenne

FROM: Sheree Brgoch, Associate Staff Engineer

DATE: November 19, 2025

SUBJECT: Contraction Modification Number 1 to Professional Service Agreement between the City of Cheyenne and Ayres Associates, for the design of 19th Street Drainage and Intersection Improvements Project.

Please find the attached Contract Modification between the City of Cheyenne and Ayres Associates for engineering services related to the design of the 19th Street Drainage and Intersection Improvements Project.

Based on findings while working on the project design the new contract items will entail additional storm sewer design, additional roadway design on Missile drive; and the addition of lighting on the 19th street bridge not included in the original project scope.

This contract modification also extends the contract deadline to March 31, 2026. This extension is needed due to the additional findings while in the design process.

Funding for this work will come from the Drainage 021-26-2618-42-43601 and Street Renovation 021-26-2616-42-43498 accounts. The total design cost associated with this contract modification will be \$63,150.00 for the services described in Exhibit A, from Ayres, dated November 3, 2025. We respectfully request your approval of this contract modification.

CITY OF CHEYENNE
CONTRACT MODIFICATION

Contract Modification: #1
Project: 19th Street Drainage and Intersection Improvements Project
Project Number: Contract No. 8046
Contractor: Ayres and Associates
Date Prepared: November 6, 2025

The above referenced contract is amended or modified as set forth in the following and these amendments and modifications of the plans and specifications are agreed to by the parties. All other aspects of the original agreement remain unchanged and in full force and effect.

I. Description of Changes

This contract modification is intended to address additional design and lighting concerns that require work that was not included in the original scope of work. The additional work is further detailed in Exhibit A attached hereto and incorporated by reference.

II. New Contract Items

- a. Additional storm sewer design on Missile drive not included in the original scope of work. The existing storm sewer system immediately south of the project was found to be undersized and will be addressed with this modification. (\$27,490.00)
- b. Additional roadway design on Missile drive not included in the original scope of work. Minimal work on Missile drive was originally anticipated. As the design progressed, it became evident that more extensive design work was necessary. (\$11,770.00)
- c. The addition of lighting on the 19th street bridge. Originally lighting was not included on the structure, and it was determined that lighting should be added for safety purposes. (\$23,890.00)

III. Schedule

No change to the schedule is necessary.

IV. Summary

Original Contract Amount	\$712,446.00
Previous Modifications	\$0.00
Contract Amount Prior to this Modification	\$0.00
This Modification	\$63,150.00
New Contract Amount	\$775,596.00

V. GL Account Information

If requesting a modification to the contract price, please list GL account # to cover the balance of this modification (if using more than (1) GL account, list the dollar amount for each respective account):

GL# 021-26-2618-42-43601 Amount: \$63,150.00

VI. Approvals:

City Project Manager: _____ Date: _____

Consultant/Contractor: _____ Date: _____

City of Cheyenne DATE: _____

_____/_____
Mayor Patrick Collins / ATTEST: City Clerk Kylie Soden

11/3/25

To: Mr. Wes Bay, Stormwater Division Manager
City of Cheyenne

Re: Contract #8046 19th St. Drainage & Intersection Amendment #1

Wes,

As we've discussed, Ayres is requesting an amendment to the contract to accommodate additional drainage design along and under Missile Drive, additional design on Missile Drive, and bridge lighting. These items have been determined to be in the best interest of the project. Below please find justifications for each.

Missile Drive Drainage

During project scoping it was assumed that the 19th Street and Old Happy Jack improvements would extend up to and tie into Missile Drive existing curb & gutter, and that no roadway or drainage improvements would be required on Missile Drive. As design progressed, it became clear the existing storm system was significantly undersized for the area draining to it, both in inlet size and pipe size. While bridge and channel improvements will help reduce flooding from Crow Creek overtopping, the road and surrounding area would still be prone to localized flooding due to inadequate surface drainage. To reduce this flooding risk, it was decided the existing stand-alone system near the 19th Street intersection, which drains directly to Crow Creek, should be improved. This system consists of 3 inlets and 630LF of pipe to be removed/replaced.

Further, drainage at the Old Happy Jack and Washington intersection is complicated by the flat existing elevations west of Missile Drive. Due to the elevation of the pipe crossing Missile Drive just north of Old Happy Jack (the basin outfall), the entire system draining this intersection is essentially flat and has minimal cover, and over time is highly likely to sediment in and require regular cleanings. In addition, future development on the vacant parcel to the northwest is likely to require upsizing and reconstructing the Missile Drive outfall pipe, and the OHJ/Washington drainage system would be stuck where it is.

To reduce future maintenance efforts and improve the overall performance of this system, it was decided that lowering and upsizing the Missile Drive outfall pipe was in the City's long-term interest. This drop in elevation, combined with upsizing the pipe, will result in a naturally flushing system that will both convey more stormwater and require less maintenance. Further, stormwater detention and water quality can easily be incorporated into this improved system in the future as development occurs on the parcel.

The estimated fee for the described work is **\$27,490**. See attached breakdown of costs for this change.

Missile Drive Roadway

As noted previously, during project scoping it was assumed that the 19th Street and Old Happy Jack improvements would extend to and tie into Missile Drive existing curb & gutter, and that no roadway or drainage improvements would be required on Missile Drive. As design progressed, it became clear the existing cross slope and curb locations on Missile Drive would not accommodate the proposed 19th Street and Old Happy Jack intersections without significant reconstruction. In addition, curb and cross slope adjustments were required to properly tie in the proposed storm sewer improvements.

The estimated fee for the described work is **\$11,770**. See attached breakdown of costs for this change.


19th Street Bridge lighting

No lighting was scoped for the project except resetting of existing street lights on wood poles that were directly impacted by the project. At the 60% plan deliverable, bridge lighting was first discussed and was agreed to be added. Lighting and electrical design will be required. Bridge design can readily accommodate conduit and foundations with no additional work.

The estimated fee for the described work is **\$23,890**. See attached breakdown of costs for this change.

The total cost for this Amendment #1 is \$63,150.

Sincerely,

A handwritten signature in blue ink, appearing to read "Nathan T. Silberhorn".

Nathan Silberhorn, PE

Senior Project Manager - Transportation

3665 JFK Parkway, Bldg. 2, Suite 100 | Fort Collins, CO 80525

Office: 970.223.5556 | Direct: 970.797.3524 | Cell: 720.235.7207

Ayres Associates Inc. | www.AyresAssociates.com



19th Street Drainage and Intersection Improvements

Change Order #1 Fee Estimate

Project Manager: Nathan Silberhorn
Client: City of Cheyenne

Task #	Task Name	Total Fee	Sub-Consultant	Direct Costs	Labor Costs	Total Hours	Senior Prof. IV	Senior PM	Prof. III	Prof. II	Prof. I	Senior Designer
	Project Plan	Fee				Hours						
	Rates						\$220.00	\$210.00	\$175.00	\$155.00	\$135.00	\$140.00
		\$63,150	\$0	\$0	\$63,150	368	8	122	4	162	24	48
Task 0	Contracting	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 1	Kickoff Meeting & Project Management	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 2	Topographic Survey	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 3	Geotechnical Investigation	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 4	Environmental Investigation & Clearance	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 5	Public Involvement	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 6	Subsurface Utility Engineering	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 7	Traffic Operations Evaluation	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 8	Floodplain Analysis	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 9	Bridge Selection & Design	\$0	\$0	\$0	\$0	0	0	0	0	0	0	0
Task 10	Urban Drainage Design (Missile Drive)	\$27,490	\$0	\$0	\$27,490	160	0	62	0	50	0	48
10.1	Basin & System Review	\$1,460	\$0	\$0	\$1,460	8		4		4		
10.2	Hydraulics Modeling	\$3,760	\$0	\$0	\$3,760	20		12		8		
10.3	Pipe Network	\$6,280	\$0	\$0	\$6,280	36		16		8		12
10.4	30% Plans	\$4,290	\$0	\$0	\$4,290	26		8		6		12
10.5	60% Plans	\$5,440	\$0	\$0	\$5,440	32		12		8		12
10.6	90% Plans	\$4,660	\$0	\$0	\$4,660	28		8		12		8
10.7	100% Plans	\$1,600	\$0	\$0	\$1,600	10		2		4		4
Task 11	Roadway Design & Plans (Missile Dr Median)	\$11,770	\$0	\$0	\$11,770	70	0	24	4	18	24	0
11.1	Horiz. and Vert. Design (median FL & NB lane)	\$1,420	\$0	\$0	\$1,420	8		4		2	2	
11.2	Layouts & Details (median openings)	\$2,300	\$0	\$0	\$2,300	12		8		4		
11.3	Sidewalks, Ramps, Driveways	\$0	\$0	\$0	\$0	0						
11.4	Control Points (Median Curb & NB Overlay)	\$1,270	\$0	\$0	\$1,270	8		2		2	4	
11.5	3D Modeling	\$620	\$0	\$0	\$620	4				4		
11.6	60% Civil Plans, Costs, & Specs (Missile)	\$2,580	\$0	\$0	\$2,580	16		4	2	2	8	
11.7	90% Civil Plans, Costs, & Specs (Missile)	\$2,310	\$0	\$0	\$2,310	14		4	2	2	6	
11.8	Final Civil Plans, Costs, & Specs (Missile)	\$1,270	\$0	\$0	\$1,270	8		2		2	4	
11.9												
Task 12	Lighting Design & Plans	\$23,890	\$0	\$0	\$23,890	138	8	36	0	94	0	0
12.1	Prelim. Lighting Layout & Utility Coordination	\$8,670	\$0	\$0	\$8,670	50	4	12		34		
12.2	90% Lighting Details, Plans, Costs	\$7,080	\$0	\$0	\$7,080	42	2	8		32		
12.3	Final Lighting Plans, Costs, & Specs	\$8,140	\$0	\$0	\$8,140	46	2	16		28		

11/3/2025